

SECTION 01010
SUMMARY OF WORK

PART 1 GENERAL

1.1 WORK COVERED BY CONTRACT DOCUMENTS

- A. Work covers the new construction (renovation) (remodeling) (re-roofing) of a _____ School located in _____, Florida.
- B. General Conditions of the Contract cover additional requirements of all Parties to the Contract.

1.2 WORK SEQUENCE

- A. Coordinate, sequence, and stage new work in accordance with approved Construction Schedules and safety plan.
- B. Coordinate access, parking, and egress of all Contractor Personnel prior to commencing construction.
- C. Construct Work in stages to provide for public and Owner's safety at all times including coordination with the local Fire Department for approval of ingress/egress with construction fencing.
- D. Working Hours shall be in accordance with the applicable City Ordinances and / or in compliance with the Owner's directions.

1.3 CONTRACTOR USE OF PREMISES

- A. Confine operations at site to areas permitted by Law, Ordinances, Permits, and Contract Documents.
- B. Do not unreasonably encumber site with materials or equipment.
- C. Refer to Section 01120 for provisions on safety, security, maintenance of access and operations, maintenance of existing utilities and services and building access restrictions.

1.4 SPECIAL REQUIREMENTS

- A. Construction personnel on any part of the school property do not allow smoking.
- B. All general contractors and subcontractor employees are required to wear plastic laminated business cards for identification and displayed at all times.
- C. The designated superintendent/foreman is to sign in and out all workmen on a daily basis. All visitors to the site shall sign in on the Site Visitors Log to be kept in the School District Construction Office trailer or other designated location.
- D. Radios, tape and C.D. players are not to be utilized on the school campus.
- E. All General Contractors and Subcontractors vehicles are to be parked in the designated construction site staging area. The staging area shown on the drawings is conceptual and may be modified prior to the commencement of the work.
- F. Notification to the School Board Project Facility Manager is required for all site accidents the same day they occur. Copies of accident reports and police reports shall be given to the School District Project Facility Manager the day they occur.
- G. No firearms or other weapons shall be brought onto the site.
- H. No animals may be brought or kept on the site.

The School District of Palm Beach County

Project Name

SDPBC Project No.

1.5 DAILY LOG

- A. The Contractor shall keep a daily log of the progress of construction and shall contain construction site equipment being utilized for each day. One copy shall be given to the School District Project Manager. The log shall be turned in daily.

1.6 ITEMS NOT IN CONTRACT

- A. Items under this contract include all work indicated on the contract documents, unless specifically noted as "Not In Contract" (N.I.C.).

PART 2 PRODUCTS

2.1 Not Used.

PART 3 EXECUTION

3.1 Not Used.

END OF SECTION