The School District of Palm Beach County Project Name SDPBC Project No.

SECTION 07 72 33 ROOF HATCHES

PART 1 GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division 1 specification sections, apply to work in this section.
- B. Modified Bitumen Membrane Roofing Section 07 52 00
- 1.2 DESCRIPTION OF WORK
 - A. Prefabricated roof hatches with integral support curbs, operable hardware, counter-flashings, and OSHA compliant hatch rail system.
- 1.3 REFERENCES
 - A. OSHA Occupational Safety and Health Administration
 - B. FM Roof Assembly Classifications
 - C. UL Fire Hazard Classifications
 - D. Florida Building Code
- 1.4 QUALITY ASSURANCE
 - A. Manufacturer: Company specializing in manufacturing the products specified in this section with minimum 5-years documented experience.
 - B. The same manufacturer shall provide roof hatches and hatch railing system.
- 1.5 SUBMITTALS
 - A. Product Data: Provide data on unit construction, size and configuration, jointing methods, attachment method, and manufacturer's installation instructions.
- 1.6 REGULATORY REQUIREMENTS
 - A. Conform to applicable Code for UL and FM requirements for fire rated roof hatches.
 - B. Provide certificate of compliance from the manufacturer indicating testing lab approval of fire or smoke rated units.

PART 2 PRODUCTS

- 2.1 MANUFACTURERS
 - A. Subject to compliance with requirements, provide products by one of the following:
 - 1. Bilco Company, Type "S-20"
 - 2. Milcor, Inc., Type "RB-1"
 - 3. Babcock-Davis Hatchways, Inc., Type "B-RHG3630"
- 2.2 ROOF HATCH SYSTEM
 - A. Integral Steel Cover: 14-gauge galvanized, prime painted steel, ASTM A653/A653M, with rigid foam insulation; integral cap flashing to receive roof flashing; extended flange for mounting.
 1. Cover to be double wall construction with 1-inch thick insulation core.
 - B. Flush Steel Cover: 14-gauge galvanized, prime painted steel with foam insulation, 22-gauge steel interior liner, and continuous neoprene gasket to provide weatherproof seal.
 - C. Gaskets: Provide Manufacturer's standard design of neoprene or EDPM.
 - D. Hardware:
 - 1. Provide compression spring operators and shock absorbers.
 - 2. Steel manual pull handle for interior and exterior operation.
 - 3. Steel hold-open arm with vinyl covered grip handle.
 - 4. Padlock hasp.

The School District of Palm Beach County Project Name SDPBC Project No.

- 5. Hinges use manufacturer's standard type.
- 2.3 HATCH RAIL SYSTEM
 - A. Furnish and install as indicated on plans hatch rail system with self-closing gate.
 - 1. HSF series by Fall Protection USA.com
 - 2. KHML series by Keehatch Roof Hatch Railing System
 - 3. RHSR series by Keehatch Roof Hatch Railing System
 - 4. Milcor safety rail system
 - 5. SRCG series by Babcock-Davis
 - 6. Approved equal
 - B. Performance characteristics:
 - 1. Hatch rail system shall satisfy the requirements of OSHA 29 CFR 1910.23 and shall meet OSHA strength requirements with a factor of safety of two.
 - C. Posts and Rails: Shall be round hot dipped galvanized steel, stainless steel, or aluminum. Fiberglass is not acceptable.
- 2.4 FABRICATION
 - A. Fabricate units to withstand 40-lb/SF (external) and 20-lb/SF (internal) loading pressure.
 1. Curb to be min. 12" high, integral with double wall construction and insulation.
 - B. Fully weld all joints and corners.
 - C. Provide for removal of condensation occurring within components or assembly.
 - D. Fit components for weather-tight assembly.

PART 3 EXECUTION

- 3.1 INSTALLATION
 - A. Install in accordance with manufacturer's instructions.
 - B. Coordinate with installation of the roofing system and related flashings for a weather-tight installation.
- 3.2 PROTECTION OF FINISHED WORK
 - A. Protect adjacent surfaces from damage by material installation.
 - B. Protect installation during construction activities.
 - C. Adjust hinges for a smooth operation.

END OF SECTION