The School District of Palm Beach County Project Name: SDPBC Project No.:

SECTION 26 29 10 ELECTRIC CONTROLS AND RELAYS

PART 1 GENERAL

- 1.1 SECTION INCLUDES
 - A) Pushbutton and selector switches
 - B) Control stations
 - C) Relays
 - D) Time-delay relays
 - E) Control power transformers
 - F) Control panels
- 1.2 REFERENCES
 - A) NEMA ICS 1 Industrial Control and Systems: General Requirements
 - B) NEMA ICS 2 and Controllers, Contactors and Overload Relays Rated 600 Volts
 - C) NEMA ICS 6 Enclosures
 - D) NEMA ST 1 Specialty Transformers (Except General Purpose Type)
- 1.3 SUBMITTALS
 - A) Submit shop drawings under provisions of Section 01 33 00.
 - B) Submit shop drawings to NEMA ICS 1 indicating control panel layouts, wiring connections and diagrams, dimensions, support points.
 - C) Submit product data under provisions of Section 01 33 00.
 - D) Submit product data for each component specified.
- 1.4 PROJECT RECORD DOCUMENTS
 - A) Submit record documents under provisions of Section 01 77 00.
 - B) Accurately record actual locations of control equipment, and revise diagrams included in Drawings to reflect actual control device connections.
- 1.5 OPERATION AND MAINTENANCE DATA
 - A) Submit operation data under provisions of Section 01 77 00.
 - B) Include instructions for adjusting and resetting time-delay relays, timers, and counters.
 - C) Submit maintenance data under provisions of Section 01 77 00.
 - D) Include recommended preventive maintenance procedures and materials.
- 1.6 QUALIFICATIONS
 - A) Manufacturer: Company specializing in manufacturing the products specified in this Section with minimum three years documented experience.

PART 2 PRODUCTS

- 2.1 CONTROL SWITCHES AND STATIONS
 - A. Contacts: NEMA ICS 2 Form C
 - B. Contact Ratings: NEMA ICS 2 as scheduled.
 - C. Pushbutton Operator: NEMA ICS 2 as scheduled.
 - D. Control Stations: NEMA ICS 2 as scheduled.
- 2.2 CONTROL RELAYS
 - A. Contacts: NEMA ICS 2 Form C.
 - B. Contact Ratings: NEMA ICS 2 as scheduled.
 - C. Coil Voltage: as scheduled.
- 2.3 TIME-DELAY RELAYS
 - A. Contacts: NEMA ICS 2 as scheduled.
 - B. Contact Ratings: NEMA ICS 2 Class A150.

The School District of Palm Beach County Project Name: SDPBC Project No.:

- C. Coil Voltage: as scheduled.
- D. Time-Delay Relays: NEMA ICS 2 as scheduled.

2.4 CONTROL POWER TRANSFORMERS

- A. Transformer: NEMA ST-1 machine tool transformer with isolated secondary winding.
- B. Power Rating: 500 VA
- C. Voltage Rating: as required

2.5 ENCLOSURES

- A. Control Station Enclosure: NEMA ICS 6 Type as required to meet conditions of installation unless indicated on the Drawings.
- B. Relay Enclosure: NEMA ICS 6 Type as required to meet conditions of installation unless indicated on the Drawings.

2.6 FABRICATION

A. Control Panels: Shop fabricated control panels to NEMA ICS 1, using cabinets and terminal blocks furnished under the provisions of Section 26 27 16.

PART 3 EXECUTION

- 3.1 INSTALLATION
 - A Install devices and equipment in accordance with manufacturer's instructions.
 - B Install individual relays and time delay relays in enclosures.
 - C Install cabinets under the provisions of Section 26 27 16.
 - D Make electrical wiring interconnections as shown on Drawings.

END OF SECTION